## OARS – the Massive Tunnel to Protect Downtown Columbus

#### PART 1









#### **OARS** Tunnel

- OARS stands for OSIS Augmentation and Relief Sewer
- OSIS stands for Olentangy Scioto Interceptor Sewer.
- The OSIS is the main sewer flowing through downtown Columbus. It was built in the 1930s and ranges in size from a 123-inch diameter pipe up to 10 ½ feet wide by 17 feet tall at Whittier Street.







#### **CSO** Consent Order

- Eliminate 12 CSOs discharging into the Scioto River along the OSIS during the "typical year"
- Whittier Street Storm Standby Tanks (WSST) 85% of all annual CSOs
- Required the City to prepare a LTCP in compliance with the requirements of the 1994 USEPA CSO Control Policy
- OARS is the key component of the LTCP







#### OARS – Designed Level of Service

- WSST overflows will be eliminated during the "typical year".
- Discharges from 12 CSOs along OSIS will be eliminated for up to a 10-year flow event. (exceeds Consent Order)
- Overflows at the JPWWTP from OARS will be limited to no more than 4 during the "typical year".
- This will keep nearly 2 Billion Gallons of sewage from overflowing into the Scioto River each year!







#### OARS - in Plain English


- Get all of the flow to the WWTP
- Maximize treatment
- Only discharge untreated flows after the WWTP(s) are full







#### Deep Tunnel Relief Sewer System









### **OARS System**


- 23,300 Feet of 20' Diameter Tunnel
- 6 Shafts 4 receive flow with special drop structures
- 4 Relief Structures
- Deep Screening Structure
- Pumping System
- Treatment Plant Connection
- River Outfall Structure































**PUBLIC UTILITIES** 







#### Shaft 1 – Stats

- Shaft 1 is the end of the line for the tunnel
- Peak flow coming in is ~ 1,700 MGD
- Shaft 1 is 215' deep and 52' in diameter
- Surface elevation is 715
- Tunnel invert is at 530
- Shaft invert elevation is 500







## Shaft 1 – OARS Diversion Structure

- Pump up to the WWTP(s)
- High level gravity flow to WWTP(s)
- Stubs for potential future HRT
- Final overflow weir to Scioto River
- Grit sumps and special baffling at the bottom of the wet well for pump performance







#### **Pumping System**

- Primary capacity requirement is to be able to dewater the OARS shafts and tunnel within 2 days
- Volume of OARS Tunnel ~ 55 MG
- Volume of Shafts ~ 5 MG
- Minimum dewatering pumping rate > 30 MGD
- Variable Gravity Head (686 530 = 156')








#### **Pumping System**

- 2 Pumps at the shaft level 20 MGD each (450 HP); run ~ 3 hours to dewater shafts
- 4 Pumps for the level 15 MGD each (800 HP); run ~ 22 hours
- 2 Grit Pumps 1 MGD each (105 HP)
- All 8 Pumps discharge to an open channel; eliminated discharge valves (saved > \$2 Million)
- All 8 pumps have VFDs to operate efficiently
- 1 Shaft Mixing System
































**PUBLIC UTILITIES** 





















## OARS starts to fill – pump to WWTP










## OARS Tunnel is full & shafts are filling – gravity flow to WWTP









OARS
Tunnel & shafts are full and WWTP(s) are at capacity









Shaft 1

Setting
Steel for the
Upper
Portion of
the Shaft











**PUBLIC UTILITIES** 













































#### Shaft 2 – Stats

- Shaft 2 is 185' deep and 42' in diameter
- Surface elevation is 715
- Shaft / Tunnel invert is at 530.3
- Cavern at the bottom of the shaft
- Two 16-foot wide channels
- Two 22-foot by 16-foot screens
- Screens have 2" clear openings








#### Shaft 2

CFD Model (Computational Fluid Dynamics)


Flow Velocity < 5 fps




















#### GENERAL PLAN AT TUNNEL & LEVEL

#### NOTES:

- ROCK AND CONCRETE REINFORCEMENT NOT SHOWN.
- FOR CONSTRUCTION JOINT AND WATERSTOP DETAILS, REFER TO SHEET TS-12.

| Pro Jec   |                                     | No.      | BY   | DATE        | REVISIONS |          | PERSONNEL | DATE        | Г |
|-----------|-------------------------------------|----------|------|-------------|-----------|----------|-----------|-------------|---|
| ě         |                                     |          | Int. | Mo./Dy./Yr. | Remorks   | Initials |           | Mo./Dy./Yr. | 1 |
| ctive     |                                     |          |      |             |           | DES.     | SN        | 01/20/10    |   |
| 7:\Dwg\Ac | JENNY<br>ENGINEERING<br>CORPORATION | $\vdash$ |      |             |           |          | OT        | 01/20/10    |   |
|           |                                     |          |      |             |           | DWN      |           |             | 1 |
|           |                                     | Н        |      |             |           | CKD      | TPK       | 01/25/10    | 1 |

CITY OF COLUMBUS, OHIO
DEPARTMENT OF PUBLIC UTILITIES
DIVISION OF SEWERAGE AND DRAINAGE

OSIS AUGMENTATION AND RELIEF SEWER — OARS PHASE 1 CIP 650704

OSS SHAFT 2 PLAN AT TUNNEL LEVEL ISSUED STATUS: CTC


DATE ISSUED: 08/20/10 Mo./0y./Yr.



**PUBLIC UTILITIES** 























CODED NOTES

TROLLEY TRACK LOCATION PER SCREEN SYSTEM MANUFACTURER.



|            |     | BY   | DATE        | REVISIONS             | PROJ | PERSONNEL | DATE        |   |
|------------|-----|------|-------------|-----------------------|------|-----------|-------------|---|
| K 200      | No. | Int. | Mo./Dy./Yr. | Remorks               |      | nitials   | Mo./Dy./Yr. | 1 |
| 2852       | Λ   | MJF  | 1/27/11     | RFP #1                |      |           |             | 1 |
|            | Δ   | MJF  | 10/1/15     | RFP FOR OSS REVISIONS | DES. | M.F       | 01/13/10    |   |
|            | 1_  |      |             |                       |      |           |             |   |
|            | _   | _    |             |                       | DWN. | WTM       | 01/13/10    |   |
| CHZIVIHILL | -   | -    |             |                       |      |           |             |   |
|            | -   | _    |             |                       | CKD. | PRS       | 01/18/10    |   |
|            |     |      |             |                       |      |           |             |   |

CITY OF COLUMBUS, OHIO
DEPARTMENT OF PUBLIC UTILITIES
DIVISION OF SEWERAGE AND DRAINAGE

OSIS AUGMENTATION AND RELIEF SEWER — OARS PHASE 1 CIP 650704

OARS SCREEN STRUCTURE SECTIONS 3

ISSUED STATUS: RFP

DATE ISSUED: 10/10/1/2015 Mo./Dy./Yr.







#### Shaft 2

# Bosker Screen Cleaning System


























#### **OARS Schedule**

Tunnel / Pumping Wet Testing – completed 4/2017

7/10/2017 – Shaft 4 OSIS Relief Structure Open

7/18/2017 – Shaft 5 OSIS Relief Structure Open

7/26/2017 – Shaft 6 OSIS Relief Structure Open

Screen System – Substantial Completion 8/2017

Full Startup ~ 8/2017

Final Restoration & Demobilization – 9/2017







#### **OARS** Operations

7/10/2017 – Shaft 4 OSIS Relief Structure Open

Within a few hours of lowering the weir gates to their final working position, a large rain event occurs:

- ~ 10 year rain event
- 1.71" that afternoon

Southerly WWTP lost power during the event Jackson Pike WWTP maxed at 160 MGD























#### **OARS** Operations

7/10/2017 – How did OARS work?

OARS filled (60 MG)

Overflowed to the river after treatment was at max.

No overflows at the WSST.

Net result = pretty good; OARS did its job.

OARS dewatered (60 MG) over the next couple days.







#### **OARS** Operations

#### 7/13/2017 – Another BIG rain event

- 2.82" of rainfall (Weather Underground Data)
- Southerly WWTP maxed at 260 MGD
- Jackson Pike WWTP maxed at 160 MGD
- OARS filled (60 MG)
- Interconnect Sewer filled
- Overflowed to the river after treatment was at max.
- WSST also overflowed.

Net result = pretty good; OARS did its job.







## **OARS Project Team**

- DLZ
- **CH2M**
- Jenny (COWI)
- Prime AE
- EMH&T
- Dynotec
- Eagon & Associates
- Multivista
- CDM Smith

- Black & Veatch
- HR Gray
- Smoot
- Aldea Services

Phase 1 – Kenny / Obayashi

Phase 2 – Trumbull

**Igel** 

**Capital Tunneling** 

Miles McClellan







### **QUESTIONS**???

Raisa Pesina Jeff Coffey

Coming up – OARS Part 2 (actual operation)





