







Jim Hewitt, PE City of Akron Scott Ankrom Hazen

Hazen

Akron Waterways Renewed!



Our Mission lies in building infrastructure that will protect public health and maintain water of the highest quality in the most cost-effective manner while providing local jobs






Agenda

- Project Overview
- Challenges
- Schedule
- Project Tasks and Details
- Dye Testing
- Construction Challenges
- Cured in Place Pipe Lining (CIPPL)
- Constructed Storm Water Wetland (CSWW)
- Questions





Akron's CSO Long Term Control Plan







Project Overview Middlebury Separation – Green Project

- LTCP modified and negotiated to Integrated Plan approach
- Separate combined sewers tributary to CSO Racks 5 and 7
- Treat portion of storm water runoff prior to discharge into the Little Cuyahoga River



Mayor
Donald L. Plusquellic
Service Director
Richard A. Merolla

City of Akron

Akron Consent Decree 2010
Final CSO Long Term Control Plan Update Report
Volume I

February 28, 2011





Department of Public Service Akron Public Utilities Bureau Water Pollution Control




Department of Public Service Akron Engineering Bureau Environmental Division


File: 2010-008-00





Project Location Middlebury Separation – Green Project











Initial Challenges Prior to Design

- Schedule: CMAR project delivery
- Determination of how to repurpose the existing CSO pipe: Sanitary vs. Strom
- How to address Clean Water connections
- Use of Green Infrastructure
- Land acquisition





Schedule Middlebury Separation – Green Project

- Notice to Proceed July 24, 2015
- Fieldwork and Design
 - > 30% Submittal September 28, 2015
 - ➤ 60% Submittal January 6, 2016
 - 90% Submittal April 13, 2016
 - 100% Submittal June 13, 2016
- Construction
 - ➤ Notice to Proceed June 21, 2016
 - Substantial Completion August 1, 2017
 - ➤ Achievement of Full Operation (AFO) October 31, 2017





- Design of selected sewer alternative
 - Re-purpose combined sewer to storm sewer and construct new sanitary sewers; or
 - Re-purpose combined sewer to sanitary sewer and construct new storm sewers
- Fieldwork to support design
- CCTV review of existing sewer along with pipe condition assessment





- 4,100 LF of new sanitary sewer: 8-in to 12-in diameter
- 15,670 LF of new storm sewer: 12-in to 48-in diameter
- 9,570 LF of CIPPL: 8-inch to 54-inch diameter
 - 2,550 LF 36-in to 54-in combined sewer converted to sanitary sewer (segmental block)





- Collection System Modeling
- Dye testing (586 home and businesses)
 - Identification of clean water connections
 - Recommended disconnection methods
- CCTV inspections and lateral launches





Constructed Storm Water Wetland (CSWW) design

Full corridor and CSWW site survey

41 soil borings, rock cores were necessary

Construction of 1.5 acre CSWW





- Land Acquisition for parcels to build CSWW
- Building Demolition
- Phase 1 and 2 Environmental Site Assessments of two City owned properties

 Asbestos abatement and demolition of two City owned buildings





Limited gas relocation

Abandon Existing Racks 5 and 7


- 3,600 LF of 6-inch water main relocation
 - Identification of non-copper water services





Dye Testing - Results


- 586 properties tested
- 56 properties improperly connected
- 2 properties technically or economically infeasible to disconnect







Dye Testing – Field Forms



Parcel ID-Test ID	Structure Type	Tested	% Roof Drained	Results	Disconnection Method	Comments
6762904-DS-1	Downspout	Yes	25	Discharges to sanitary sewer	4	6762904-Out-1
6762904-DS-2	Downspout	Yes	25	Discharges to sanitary sewer	4	6762904-Out-1
6762904-DS-3	Downspout	Yes	25	Discharges to sanitary sewer	1	6762904-Out-1
6762904-DS-4	Downspout	Yes	25	Discharges to sanitary sewer	1	6762904-Out-1
6762904-DS-5	Downspout	Yes	0	Discharges to sanitary sewer	1	6762904-Out-2
6762904-DS-6	Downspout	Yes	0	Discharges to sanitary sewer	1	6762904-Out-2
6762904-DS-7	Downspout	Yes	0	Discharges to sanitary sewer	4	6762904-Out-2
6762904-DS-8	Downspout	Yes	0	Discharges to sanitary sewer	4	6762904-Out-2
6762904-D5-9	Downspout	Yes	0	Discharges to sanitary sewer	1	6762904-Out-3
6762904-DS-10	Downspout	Yes	0	Discharges to sanitary sewer	1	6762904-Out-3
6762904-DS-11	Downspout	Yes	0	Surface Discharge	No Work Required	
6762904-DS-13	Downspout	Yes	0	Surface Discharge	No Work Required	
6762904-DS-14	Downspout	Yes	0	Surface Discharge	No Work Required	
6762904-DS-15	Downspout	Yes	0	Surface Discharge	No Work Required	
6762904-DS-16	Downspout	Yes	0	Surface Discharge	No Work Required	
6762904-DS-17	Downspout	Yes	0	Surface Discharge	No Work Required	
6762904-DS-18	Catch Basin	Yes	0	Discharges to storm sewer	No Work Required	6762904-Out-7
6762904-DS-19	Catch Basin	Yes	0	Discharges to storm sewer	No Work Required	6762904-Out-7
6762904-DS-20	Catch Basin	Yes	0	Discharges to storm sewer	No Work Required	6762904-Out-7
6762904-DS-21	Catch Basin	Yes	0	Discharges to storm sewer	No Work Required	6762904-Out-7






Middlebury Separation - Green Project (CSO Rack 5 & 7) Clean Water Connection Investigation Results







Dye Testing – Proposed Removal Plans







Challenging Construction Areas

Fairbanks Place

- 20 ft and 27 ft right-of-way
- 12 ft and 18 ft wide concrete street
- House and retaining walls encroaching right-of-way
- Relocation of water main
- New storm & sanitary sewers in "common trench"
- Relocation of natural gas line







Challenging Construction Areas

Black Street


- R-o-W varies: 20 ft & 40 ft
- Existing 36-in & 42-in combined sewer
- New 36-in storm sewer
- Relocate water main
- Brick street restoration








Challenging Construction Areas Exchange & Arlington (water and sewers)








Challenging Construction Areas Exchange & Arlington (sewers only)








Challenging Construction Areas Exchange & Arlington (all underground utilities)







Challenging Construction Areas Exchange & Arlington (all underground utilities)















Cured In Place Pipe Lining (CIPPL)

- 9,570 LF of CIPPL
- All segmental block sewers converted to sanitary sewer
- Existing sewers with critical defect scores of 4 or 5








Constructed Storm Water Wetland (CSWW) Design Criteria

- Capture first ¾-in of rainfall
- "Treat" water quality volume (WQv) 183,000 ft³
- Bypass flow in excess of the water quality flow
- Empty less than 50% of WQv after 8 hours
- Minimize areas of standing water after 24 hours
- Provide pretreatment for gross solids and TSS removal
- Prioritize use of native vegetation





CSWW – Contributing Drainage Area





Rack 7

108 ac

44%

89,000 ft³

Rack 5

83 ac

61%










CSWW - Proposed Site Layout







Pretreatment Hydrodynamic Separators



Contech CDS





Subsurface Gravel Wetland







CSWW – Site Construction







CSWW – Site Construction







CSWW – Site Construction







CSWW -Site Construction








Between Storm Events








During a Storm Event







During a Storm Event











Questions



Jim Hewitt, PE

330-735-2355

jhewitt@akronohio.gov

Scott Ankrom

330-835-9585

sankrom@hazenandsawyer.com

